



ASHOKA ENDURANCE ROAD DEVELOPERS PVT LTD

WORK ORDER

To,

M/s. LK Electricals

Add:- Behind Bahuuddeshiya Bhayan,

At PO. Kurkheda, Gadchiroli,

Maharashtra, 441209

PAN No- HRZPK4576A

AADHAR No- 7407 5971 5190

Mob. No- 8275405340

GSTIN No- 27HRZPK4576A1Z5

Date: 18.10.2024

AERDPL/1458/012

Kind Attn:- Mr. Nitesh Abhimanyu Khobragade

Sub:- Development of Distribution Infrastructure at Gadchiroli District & part of Chandrapur district of Maharashtra under the Revamped Reforms-based and Results-linked, Distribution Sector Scheme (RDSS)

Project:- RDSS MH GADCHIROLI T-10 (Division:- Gadchiroli)

Ref:- Discussion with Project Manager.

Dear Sir,

We refer to the discussions with respect to the above subject, MSEDCL and based on your representation of having the required expertise, experience and resources in executing similar works, we are pleased to appoint you as our Sub-Contractor and issue this work order to you as per terms & conditions mentioned below/ attached herewith

Part A:- Detailed Scope of works:-

The said Project has been awarded by M/s Ashoka Buildcon Ltd., Nashik to M/s. Ashoka Endurance Road Developer Pvt Ltd (herein after referred as "AERDPL").

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



ABL & **AERDPL** have executed an agreement on 07-06-2024 ("Main Contract") and accordingly, Work has to be executed as per the **ABL** Technical Specification (TS) terms & conditions and FQP (Field Quality Plan) provided in the Main contract **ABL**.

M/s. LK Electricals shall ensure best quality of work and ensure compliance as per provided specifications, design, adopting standard method of construction and conditions of Main contract and due diligently, true to the specifications as laid down in the Main Contract and up to the satisfaction and requirement of **ABL/AERDPL**.

Following are the key deliverables of **scope of work**:

The Scope of works to be executed for site survey, planning, design, engineering, assembly testing, loading, transportation, unloading, insurance, delivery at site, handling, storage, installation, testing, commissioning and documentation of all items/material required to complete the following works in the **Chandrapur Zone** which inter-alia include **Feeder Separation** Activities such as 11 kV HT Line, LT line, 100 KVA DTC, 11 KV Feeder Bay, SDT, AB Switch, Double pole and single pole cut point, 11 kV AB Cable, 95 Sq. mm XLPE UG Cable and etc.. (Hereinafter referred to as Scope of works).

Part B:- Work Order value

Total Work order value is as per **Annexure-I** excluding GST and including all types of consumable materials, taxes, Royalties, duties, levies, cess etc. labour charges, fuel, oil, lubricants, transportation, equipment's, tools and tackels, safety apparatus, supervision, overheads, profits and / or any other incidentals required for the execution of this contract etc; both present and future, applicable to this work order for the works awarded to sub-contractor. The detail price break up of the scope of works is enclosed as **Annexure-I**.

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



The above Work Order quantity and accordingly its value may vary as per the site/ MSEDCL/ABL requirement and scope finalized by MSEDCL. All rates mentioned in **Annexure-I** are indicative, Billing of Completed work will be done based on the unit rates of each item consumed in the quantity of Activity completed according to the rate of each item mentioned in the **Annexure-I** & for the quantity of item certified by **ABL/ AERDPL**.

Part C: - Unit Rate of Work

As per **Annexure-I**

Note: Quantity is tentative; payment shall be made on actual work done/quantity of works executed and measurement taken at site by Site Engineer In-charge and quantity accepted by **ABL**. All unit prices are on the firm basis, no price variation/ escalation is applicable to this Work order & payable to the sub-contractor on any account

Part D: COMPLETION SCHEDULE:

- i. Time is essence of this contract/ Work Order **M/s. LK Electricals** has to maintain the time schedule. The Total works has to be completed to the satisfaction of AERDPL, **ABL**. The feeder (including all related activities) shall be completed within one month/due date of AERDPL milestone.
- ii. Sub-contractor shall submit the execution program to AERDPL's site representative within 03 days from the date of issuance of this work order and mutually finalize the same within 3 days after submission of the same. AERDPL shall have rights to modify the same as per requirement.
- iii. Works shall commence within 7 days from the date of receipt of this Work order.
- iv. Further Sub-Contractor shall submit the daily & weekly progress reports to AERDPL Nashik HO and field office.

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



- v. In the event if AERDPL, in its sole judgment, Sub-Contractor's progress has fallen behind the scheduled progress /as per execution programmer and it becomes apparent that the forecast completion date is likely to be later than the Intended Completion Date, then the Sub-Contractor shall become liable to pay interim penalties for such default to the AERDPL at the rates 1% per week of total cost of activity. AERDPL has the rights to recover the Interim penalty from the R.A. Bills or Final bills. If the values of the interim payments are not sufficient to recover such interim penalties, then the **AERDPL** have rights to recover from security submitted by Sub-contractor.
- vi. If the Sub-contractor fails to improve the progress of works, within 7 days on issuing notice to cure in such case, **AERDPL** shall have the right to terminate forthwith. **AERDPL** will complete the balance work by deploying its own resources or by deploying another contractor at the risk and cost of Sub-contractor. In such case, Sub-contractor agrees that, he will not obstruct works to be carried by other resources/ other contractor deployed by **AERDPL**.
- vii. If the Sub-Contractor fails to complete the works within time limit as stipulated in this work order, the Sub-Contractor shall pay Liquidated damages to **AERDPL** for delay. The Liquidated damages to be calculated at the rate of 1% of total contract price per week of delay subjected to maximum 10% of contract price for entire scope of work. **AERDPL** has the right to recover such liquidated damages from the R.A. Bills or Final bills. If the values of the interim payments/final payment are not sufficient to recover such Liquidated damages, then the **AERDPL** have a right to recover from security submitted by Sub-contractor.

Part E: - Payment Schedule –

1. **85%** payment shall be released by **AERDPL** after completion of Erection works, Testing & commissioning of Facility, and on submission of relevant documents indicated herein under:

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



- a) Submission of invoice
- b) Completion of erection works including maintaining proper records of erection/constructions as per FQP (Field Quality Plan).
- c) Attending all Quality compliances.
- d) Commissioning/ charging of activity/ facility.
- e) Certification of Joint Measurement (i.e. between **AERDPL**–ABL & **AERDPL**-Subcontractor) & on submission of other documents as per the **AERDPL**, ABL requirement.
- f) Signing of Handing over taking over certificate (HOTO), Completion certificate, Operational acceptance Certificate by concern authority of ABL.
- g) Submission of Royalty challans towards the sand, minerals, earthen materials etc.;
- h) Subcontractor shall submit the location wise material reconciliation to **AERDPL** along with materials utilized for erection, testing and commissioning of claimed activity.

Note:

- i. Payment will be released strictly according to the Qty. of items erected and certified by **AERDPL** & ABL.
 - ii. Payment will be coming through quality department if subcontractor will not provide the pole to pole concreting videos with RA Bill then payment shall not be released. After providing the Concreting video of poles and if found in order, same shall be released.
2. **10%** Payment shall be released after successful commissioning and overall completion of all allotted works, final Material reconciliation, removing all defects, getting final clearance certificates from ABL and after:
- a) Certifications of works by **AERDPL**, ABL.
 - b) Signing of Handing over taking over certificate (HOTO), Completion certificate, Operational acceptance Certificate by concern authority of ABL.

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



- c) Signing/ Submission of all test reports, drawings, as per Main contract, jointly witnessed and signed by **AERDPL** and ABL, as built drawings along with changes are incorporated if any, material reconciliation and handing over certificate from ABL for the completed activity.
- d) Commissioning of overall activity or allotted works, overall completion certificate from ABL to **AERDPL**.
- e) Submission of location wise material reconciliation data for the entire work.
- f) Deduction of amount of short items found in material reconciliation.

The value of such short items will be calculated as per the market rates or the contractual rate of each item whichever is maximum plus 10% material handling and financial cost for the procurement of such material. If the recovery amount is more than 10% of balance amount then **AERDPL** shall have right to recover from security submitted by the sub-contractor.

- 3. **5%** payment shall be released after successful completion of the complete package and after completion of defect liability period as per the terms & conditions of Main contract & after receipt of final 10% payment from ABL to **AERDPL**, after release of performance bank guarantee submitted to ABL by **AERDPL** and:
 - a) On the completion of Entire scope of work of project and after getting the final handing over and clearance certificate from ABL as per Main contract.
 - b) After submission of "No claim certificate" on appropriate stamp paper by Sub-contractor to **AERDPL**.
 - c) On fulfillment of all statutory liabilities such as insurance, provident fund, works contract tax, ESIC etc.

Note: At the time of finalization and closure of account; if any recovery or debit on sub-contractor he shall deposit such deficit amount in **AERDPL's** bank accounts within 7 days from the date of notification of closure if sub-contractor fails to do so then **AERDPL** shall have a right to recover the same from security submitted by sub-contractor.

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



Part F: Taxes & Duties

- a) **AERDPL** will deduct applicable TDS, WCT and Labour cess. Rates given are Exclusive of GST, same will be paid on production of valid proof of payment made to GST authority & submission of monthly GST return.
- b) All the rates are inclusive of royalties, duties, levies, Cess etc.; however, only GST will be paid extra.
- c) Sub-Contractor shall submit Royalty paid challan/proof for the civil materials along with each RA bills. All the applicable taxes/GST must be shown separately in respective RA Bill along with declaration as required under the respective laws/ acts.
- d) All statutory compliances viz PF, ESIC, GST, Labour cess, royalties, duties etc.; shall be complied timely by the Sub-contractor. In case of any notice or demand by any department to **AERDPL**, Sub-contractor shall submit the same within 7 days; or in case of failure, same shall be recovered by **AERDPL** from any security or due payments payable to the Sub-contractor.

Part G: Validity of Work Order

This work order is valid for 18 months from the date of issue of Work order or as per decision of **AERDPL**.

Part H: Monthly Documents Required:-

- 1. Form A (Certified copy of Employment register having employee's details).
- 2. Form B (As per state format) Wages Register.
- 3. Form C (As per state format) Muster Roll.
- 4. In and out time Register.
- 5. Certified copy of wage slip
- 6. Certified copy of Employment card.
- 7. Certified copy of Service certificate for left employees.

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



8. Employee ID Proof (Adhar Card)
9. Overtime register cum declaration.
10. Form D under equal remuneration Act.
11. Register of unpaid wages.
12. Certified copy of PF/ESI monthly ECR.
13. Police verification statement of all labours, supervisor, manager etc. should be submitted on regular basis. (Whenever new manpower is utilize for this activity)
14. Copy of PF challan
15. PF TRRN summary/Paid confirmation.
16. Salary credit to the bank Account confirmation details.
17. Medical fitness certificate.
18. Screening form of all labours with photo and Adhar card.
19. Undertaking cum affidavit on monthly compliance under various act. (Minimum wages compliance including deduction of PF & ESIC)

Part I: Other Terms & Conditions:-

1. All terms and conditions as mentioned in the Main Contract are applicable to this sub-contract/work order in addition to the terms mentioned herein for performance of the Sub-Contract Works. Further all rates mentioned in the **Annexure-I** applicable on this Sub-Contract /Work Order and binding on Sub-contractor. The Sub-Contractor confirms that he has full knowledge and complete understanding of the provisions of the Main Contract as the same are applicable to the Sub-Contract Work.
2. Sub-Contractor shall provide at its own cost all labour, materials/tools & tackles, construction plant & machinery and everything whether of a permanent or temporary nature, required for execution & satisfactory completion of the said Sub-Contract Works, as required by the Main Contract. Sub- Contractor shall take utmost care to ensure best quality of work and ensure compliance as per provided specifications, design, adopting standard method of construction and conditions of Main Contract. Sub- Contractor shall be responsible for removal of all defects in Sub-

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



Contract Work executed, at no extra costs till completion and thereafter till the end of defect liability period, as stipulated in the Main Contract.

3. Subcontractor should ensure that concreting shall be done as per requisite quantity, if not found work will be rejected and expenses occurred for doing rework shall be borne by subcontractor.
4. Wherever applicable, the Survey, design & drawing preparation, Supervision & approval shall be taken from **AERDPL**, ABL.
5. Sub-contractor shall execute the Work as per General arrangement drawings & specification provided by **AERDPL**/ABL. If any change/modification is suggested by **AERDPL**/ABL; then such changes/modification as suggested shall be done by the Sub-contractor at his own cost. If Sub-contractor fails to do the execution as per given drawings, same shall be re executed by Sub-contractor at his own cost.
6. At the time of signing of work order sub-contractor shall provide the security to the **AERDPL** towards the sums recoverable for facility work, non-compliances, materials reconciliation, under performance & penalties as envisaged in this work order from time to time. **AERDPL** shall have right to recover any due from such security; for which no objection will be raised by **M/s. LK Electricals** in future. The sub-contractor specifically agreed that, such security will be treated as legal debt and liability towards **AERDPL**.
7. Indemnity Bond: Sub-Contractor is the custodian of all material issued to Sub-contractor by **AERDPL**. The Sub-Contractor shall execute an indemnity bond for the full value of the material, in the Performa to be furnished by **AERDPL** indemnifying **AERDPL**, ABL against any loss or damages of material. This indemnity bond shall be valid till the date of testing, commissioning and handing over all the works to the complete satisfaction of ABL & **AERDPL** and return of all balance materials or on acceptance of debit against the shortfall (if any) of materials and till the closure of accounts with the **AERDPL**.

8.

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



9. Sub-contractor will be responsible to collect the material from **AERDPL**'s central store after clearing of all requisite documentation. The materials will not be issued to anyone other than Sub-Contractor or Authorized person deputed by Sub-Contractor. Sub-contractor must submit the authorization letter of authorized person as per format of **AERDPL**. All charges required for transportation, loading, unloading of issued materials shall be exclusively borne by Sub-contractor. Further all charges required for transportation, loading, unloading of dismantle material up to **AERDPL** store / ABL store (in case of and materials dismantles in any R &M or Conversion activity) shall be exclusively borne by Sub-contractor.
10. Sub-contractor has to ensure that they will consume all the issued materials within 60 days from the date of issuance of material. If issued material remains idle /unutilized for the period more than 60 days, **AERDPL** will recover interest @ 18% per annum of the total cost of the idle materials for the period beyond 60 days, including 10% material handling charges. The cost of material will be calculated as per the market rate or actual purchase cost (including cost incurred for procurement of such material) or cost as per the main contract, whichever is higher.
11. The Sub-contractor shall ensure round the clock security and safety of all material issued by **AERDPL** or directly obtained from the ABL on behalf of **AERDPL** during installation work and till the issuance of completion certificate, taking over Certificate, Operational acceptance by ABL, at no additional cost to **AERDPL**.
12. The Sub-contractor shall arrange storage for his material & equipment and accommodation for his workers & staff as per desired standards.
13. The Sub-contractor will be responsible for the security of the entire installation/equipment/material within his scope of work including posting of the watchman, security guard till the final handing over of the installation, issuance of completion certificate, taking over Certificate, Operational acceptance by ABL. The Sub-contractor shall provide at his own cost all lights illumination required for watch and ward, guards etc. as necessary to ensure that there is no pilferage/theft etc. within his scope of work. In case of theft/loss of materials, twice of the purchase cost amount shall be recovered from your security or balance payment.

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



14. During execution if any RoW arises, RoW resolving is in the scope of Subcontractor, **AERDPL** /ABL will assist to subcontractor.
15. If any discrepancy arises during execution, after completion of works and or during the defect liability period, it is responsibility of the Sub-contractor to rectify the same & the expenses incurred for the rectification work will be borne by the Sub-contractor exclusively and also sub-contractor shall pay amount deducted towards penalty against major, minor & critical defects or any other account by MSEDCL from the **AERDPL** dues for the works allotted to the sub-contractor. **AERDPL** shall have rights to recover such payment from due payment of Sub-contractor, in case sub-contractor fails to make such payment"
16. Sub-Contractor has to take all necessary safety precautions of its workmen as per industry standards & as per site conditions. Sub-Contractor will be responsible for the safety of his /her safety and equipment's deployed at site during execution of work & shall provide all personal protective equipment's like Helmet, Jacket, Safety Shoes etc. and Sub-contractor shall ensure that all safety standards will be adopting by workmen during works and take all necessary precautions as applicable. Adequate safety precautions shall be taken while working during night via providing lamps with red light reflectors safety reflectors with red band / strips, torches and red jacket for crew. Sub-Contractor to ensure availability of all safety related accessories such as safety shoes, hand gloves, helmet etc. for their labours. The Sub-Contractor will have to issue Employment cards in approved format as per relevant rules and regulations.
17. The Sub-Contractor will follow strictly all safety rules and regulations applicable to the project. If any accident happens to any of his workmen the Sub-Contractor will submit information including all necessary documents without causing any delay to the Project In-charge of **AERDPL** & Head Office Nashik, the details regarding the workman and all the relevant data required to fill up the reports as required by ESIC (if applicable) / or any other Insurance Company and to take further necessary action. This information should be submitted to the Site office of the **AERDPL** & Head Office Nashik by the Sub-contractor only, failure to do so may entitle to

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



withhold any dues. The Sub-Contractor will not employ the injured workman unless a fitness certificate from authorized Medical Officer is produced by the workmen same shall be ensured by the sub-contractor.

18. If the Labour/Employees meet with an accident while working in the system resulting in death or loss of earning capacity of the labor /Employee, his legal heir(s) / concerned Labour/Employee (in case of loss of earning capacity) shall be entitled to get compensation as per Workmen Compensation Act, 1923 (amendment, if any) from the Sub-Contractor. Sub-contractor is overall responsible for any accident happen at site during execution of work.
19. Accident Claim: No accident claim will be entertained by **AERDPL** for accident and non-insurance as indicated following any accident happening on site by misuse of its own driver, operator/helpers, labours will be the responsibility of the Sub-contractor.
20. Provident Fund: Sub-Contractor will submit the copies of proof of payment to PF Authority (monthly) by the 7th of next month to **AERDPL's** Nashik office.
21. The Sub-contractor will obtain insurance for the Labour / Employee deployed for the allotted works.
22. The Sub-contractor shall hold valid licence allotted through concerned department of competent authority. The sub-contractor shall hold adequate expertise & experience in the said field for doing the said job. All the works are to be carried out under license holder supervisor from your side.
23. The Sub-contractor will not appoint any child labour (labour less than 18 year old) on the project.
24. Amendments: This Work Order may be amended, by mutual consent, in writing specifically and which shall be duly signed by authorized representative of **M/s. LK Electricals** and **M/s. AERDPL**.
25. If in the opinion and discretion of the **AERDPL's** representative under whose supervision the work is done, if it is found that the Sub-Contractor employs inadequate number of men of which they fail to proceed with the work with reasonable speed or does not execute it in a satisfactory and workman like manner

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory

or if in accordance with the terms and conditions of the contract/work order or refuses or neglects to make such alterations as **AERDPL**'s representative may require time to time, the **AERDPL** shall get the work done through **AERDPL**'s labour or any other Contractor at Sub-contractor's risk and cost same will be recovered from the Sub-Contractor.

26. The payment of workmen/labours, employee deployed at sites by the sub-contractor will be in the exclusive scope of the Sub-contractor. **AERDPL** will not be liable or responsible for non-payment/short payments of wages done by Sub-contractor.
27. All works shall be carried out as per Indian Electricity Rules, 1956 and its amendment. Erection Order and the conditions of Main contract, guidelines, circular, terms and conditions. Indian Standard Specifications and codes / and or as per MSEDCL specification, which will be verified by the representative of ABL etc. periodically. **AERDPL**'s /ABL instructions in writing, shall be binding on the Sub-Contractor.
28. All the damages including interest, penalty etc. suffered by **AERDPL** due to non-payment and non-compliance of statutory obligations and non-payment of Duties, Taxes, Cess, and Surcharge etc. by the Sub-Contractor shall be deducted and recovered from Sub-contractor R.A bills /Final bills/ Security submitted by the sub-contractor.
29. The Sub-contractor shall submit the copies of all the Statutory Registration Certificate e.g. GST, PAN, TIN, Electrical Contractor License valid in Maharashtra, PF, ESI, Labour License, copy of workmen compensation insurance policy etc. the said list are only indicative but not exhaustive.
30. Sub-Contractor shall comply with all statutory rules and regulations under the various acts/Laws for due and proper execution of the said work. The Sub-Contractor shall be registered under the various Laws, applicable to the Sub-Contractor, in connection with the performance of the Sub-Contract Works. The proof of such registration shall be made available to **AERDPL**. Any liability towards your worker/employee due to any accident arises same will be borne by 'Sub-Contractor'.

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



31. Sub-Contractor shall pay Labour Cess as applicable on the value of the bill claimed. The said Labour Cess will be deducted and recovered from the bill claimed and/ or amount payable to Sub-Contractor. The prices mentioned in the Annexure-I is inclusive of Labour cess.
32. Deployment of Key personal: Minimum Key Personal shall be deployed by the Sub-contractor at site. Sub-Contractor will deploy Technical Staff / Engineers to supervise the work as directed by **AERDPL**.
33. Under no circumstances sub-contractor shall sublet the contract awarded to it by **AERDPL**. In case of any deviation of this clause may attract termination of sub-contract without any notice.
34. In case the Sub-Contractor/his labour, Employee caused damage any of the **AERDPL**'s or any other agency's property or persons while execution of this contract then, the Sub-contractor shall be held liable & responsible for the same which will be recovered from the Sub-contractor.
35. Idle time payment: Sub-Contractor shall not be entitled to any idle time payment for his work force / staff /construction machinery & other resources etc., on any ground whatsoever.
36. The work shall be completed only after the Sub-Contractor has obtained Completion Certificate from **AERDPL**.
37. The location of work fronts may change as per MSEDCL / M/s. Ashoka Buildcon Limited/ PMA requirements, instruction from time to time. In such cases no claim for mobilization/ demobilization, loading/ unloading of materials whatsoever, shall payable to Sub-contractor.
38. **AERDPL** will not be liable to pay any amount to the Party / Agency / Persons with whom the Sub-contractor shall deal while executing the scope of works allotted to sub-contractor. Sub-contractor shall make its own arrangements to make the payment to the concerned Party / Agency / Persons worked with sub-contractor irrespective of payment due with **AERDPL**.
39. Project Site Data: You have inspected & examined the Project site and its surroundings and to have satisfied yourself before entering into this contract, as to;

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



- a) The form & the nature of the Project site;
- b) The hydrological & climatic conditions;
- c) The extent and the nature of the Works and resources (Men, Materials, Plant & Machinery) necessary for the execution and the completion of the works and the remedying of any defects, if any, therein;

AERDPL's responsibility shall be limited to:

- a) Monitoring of the progress of Work and Co-ordinate with MSEDCL/PMA execution through a representative as and when required, at the discretion of **AERDPL**. It will be depend on work progress, development of site reported by Sub-contractor periodically, weekly, and daily & monthly as per **AERDPL** requirement.
- b) Providing all the required material for electrical works at the central store.
- c) Coordinating with Employer or Employers representative.

40. In case of the Scope of works added or deleted or revised, milestone comprising the altered scope shall be submitted by Sub-contractor, for approval to **AERDPL** time to time.

41. Sub-Contractor should ensure that no one from his labour/employee or contractor himself will demand any money from the Consumer/Public against the work to be executed. If any such instances are noticed immediate Legal/Criminal action as per the contracts & law will be taken on him. Contractor should take note of the same.

42. Dispute Resolution Process:

- a) Any dispute/s arising between the parties out of or relating to this Agreement shall be resolved through good faith negotiations between authorized representatives of each Party. Such negotiations shall commence within [45] days of the written notice of the Dispute being served to other party.
- b) Mediation/ Conciliation: If the Parties are unable to resolve dispute/s through negotiation within [120] days of the commencement of negotiations, such dispute/s shall be submitted to Mediation. The mediation shall be conducted in Nashik, Maharashtra in accordance with the provisions of the Mediation Act,

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



2023 and any subsequent amendment. The Parties shall mutually appoint a Sole Mediator who shall be a Sr. Techno-legal/Technical professional having more than 20 Years of experience. The language of Mediation Proceedings shall be English. The costs of the mediation shall be shared equally by the Parties. The mediation process and Settlement Agreement, if any, shall be governed by, construed and take effect in accordance with the substantive laws of Maharashtra, India. Competent court at Nashik shall have exclusive jurisdiction in this regard.

C) In case the parties fail to resolve the dispute/s through Mediation , the same (such disputes) shall only be adjudicated by Sole Arbitrator selected mutually by the Parties. Arbitration shall be conducted as per the provisions of Arbitration and Conciliation Act 1996 and as amended from time to time. The Venue and Seat of the Arbitration shall be at Nashik and the language of the Arbitral proceedings shall be English. The award shall be a reasoned award. Competent court at Nashik shall have exclusive jurisdiction in this regard.

43. Governing Law: This Work order shall be governed by and construed in accordance with the applicable laws of India, and subject to the Courts of Nashik only shall have the exclusive jurisdiction in the matters arising there under.

44. **M/s. LK Electricals** will be held solely responsible in all respect for any liability/liabilities may occur during execution of work, delay in performance, non-performance or part failure or full-failure, complete financial liabilities, claims from suppliers, sub-contractor, employees, agents, government authorities, government officials, third person outside agencies for damages, obligations, compensation, loss, cost, omission or default or mistake etc.

45. Any loss/damages suffered by **AERDPL** and or ABL under the Main Contract resulting from delay in performance of Sub-Contract shall be to the account of the Sub-contractor.

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



46. Sub-Contractor fully understands and acknowledges that any act or omission by Sub-Contractor shall have impact on the Main Contract and the responsibility for all the consequences arising from such act or omission shall lie on Sub-Contractor. The Sub-Contractor shall indemnify **AERDPL** against any and every liability which **AERDPL** may incur itself or to any other person whomsoever and against all claims, demands, proceedings, damages, costs and expenses made against or incurred by **AERDPL** by

reason of any breach of these terms and/or the terms of the Main Contract by the Sub-contractor.

47. Severability: In the event of any provision, clause hereof or the application thereof in any circumstances is held to be invalid or unenforceable, such invalidity or unenforceability shall not affect the validity or enforceability of the remainder hereof.

48. By accepting the terms & conditions of this work order, the Sub-Contractor is deemed to have agreed to the terms and conditions stipulated under the Main Contract.

49. You are requested to comply with further documentary/ statutory compliances to work order. Kindly proceed with survey and site mobilizations immediately.

This work order is being issued in duplicate. Please return one copy duly signed and stamped on each page as unconditional acceptance of this work order by an authorized person.

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



ASHOKA ENDURANCE ROAD DEVELOPERS PVT LTD

ANNEXTURE-I

Activity No	Activity Description	UoM	Total Qty	unit Rate	Total Amt
603B	Erection, Testing & Commissioning of 11kv Feeder Bay with Gantry Structure & PT	NO	1.00	1,53,550.02	1,53,550.02
1230	Erection, Testing & Commissioning of 11 KV Specially Designed Transformer with all accessories, Control cable , Relays, contactors, Earthing etc.	NO	1.00	24,010.00	24,010.00
916	Erection, Testing & Commissioning of 11kv 3Cx95 mm2 XLPE UG cable	KM	-	2,50,000.00	-
934A	Erection, Testing & Commissioning of 11 KV Single circuit Pin type with AB cable 3Cx95+70 sqmm on 100x116 mm 10 mtr RSJ poles	KM	-	1,10,000.78	-
1220	Erection, Testing & Commissioning of 11/0.4kv, 100kva Distribution Transformer Centre on RSJ 100x116mm, 11mtr, with kitkat Dist. Box	NO	19.00	23,517.00	4,46,823.00
1425A	Erection, Testing & Commissioning of 3 phase 5 wire LT line with AAAC 55 sqmm for phase and ACSR Weasel for neutral on PSC pole, 8 mtr., 140 Kg	KM	10.00	41,010.00	4,10,100.00
6723	Erection, Testing & Commissioning of 11 kV A.B. Switch 400 Amp with DP structure.	NO	7.00	11,500.25	80,501.75
924	Erection, Testing & Commissioning of Single pole cut point Structure for 11kv line on RSJ 152x152, 11 m long pole with concreting	NO	-	7,499.40	-
922	Erection, Testing & Commissioning of Double pole cut point Structure for 11kv line on RSJ 116x100, 11 m long pole	NO	-	10,898.73	-
919	Erection, Testing & Commissioning of River crossing with 55sqmm overhaed on 152X152 mm, 13mtr RSJ poles	NO	1.00	30,000.10	30,000.10
907	Erection, Testing & Commissioning of RSJ 116x100, 9 m long with V Cross arm, Top fitting and allied material like AAAC Conductor, Insulators, barbed Wire, GI wire, stay wire etc.	KM	39.00	1,16,600.00	45,47,400.00

Basic Amt	56,92,384.87
GST	10,24,629.28
Total Amt	67,17,014.15

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory

						100%	85%	1.00
11 KV FEEDER BAY with Gantry structure & PT 603 B								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	85%	Total Amt (85%)
1	L.As. 11 KV (Gapless type) with disconnector	Set	1	1.00	800	800	680	680.00
2	11 KV Isolators with EB (800 A)	Set	1	1.00	9000	9000	7650	7,650.00
3	11 KV Isolators without EB (800 Amp.)	Set	1	1.00	9000	9000	7650	7,650.00
4	11 KV VCB 400 A Outdoor	Set	1	1.00	9000	9000	7650	7,650.00
5	11 KV PT	Set	3	3.00	2000	6000	1700	5,100.00
6	11 KV CT 400 - 200 / 5 - 5 Outdoor	No	3	3.00	2333.34	7000.02	1983.339	5,950.02
7	C&R Panel for 11 kv Outgoing Feeder OD	Nos.	1	1.00	7000	7000	5950	5,950.00
8	Structure and foundation cables, clamps, painting etc.as per sheet (A+B+C+D+F)	L.S.	1	1.00	75000	75000	63750	63,750.00
9	Marshalling Box	No	1	1.00	900	900	765	765.00
10	Earthing as per Sheet (E) 11 KV Bay	L.S.	1	1.00	11300	11300	9605	9,605.00
11	MS Steel for RCC works etc	Job	1	1.00	7500	7500	6375	6,375.00
12	Metal Spreading 20 mm, 40 mm stone	M3	5	4.95	1000	4950	850	4,207.50
13	Water arrangment if require	Job	1	1.00	1800	1800	1530	1,530.00
14	Miscellaneous materials for 11KV Bay i.e Gland, Lug, ferruler, PVC Pipe etc.	JOB	1	1.00	4300	4300	3655	3,655.00
	Cost of material				140933.34	153550.02	119793.339	130517.517

								100%	10%
11 KV FEEDER BAY with Gantry structure & PT 603 B									
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	10%	Total Amt (10%)	
1	L.As. 11 KV (Gapless type) with disconnector	Set	1	1.00	800	800	80	80.00	
2	11 KV Isolators with EB (800 A)	Set	1	1.00	9000	9000	900	900.00	
3	11 KV Isolators without EB (800 Amp.)	Set	1	1.00	9000	9000	900	900.00	
4	11 KV VCB 400 A Outdoor	Set	1	1.00	9000	9000	900	900.00	
5	11 KV PT	Set	3	3.00	2000	6000	200	600.00	
6	11 KV CT 400 - 200 / 5 - 5 Outdoor	No	3	3.00	2333.34	7000.02	233.334	700.00	
7	C&R Panel for 11 kv Outgoing Feeder OD	Nos.	1	1.00	7000	7000	700	700.00	
8	Structure and foundation cables, clamps, painting etc.as per sheet (A+B+C+D+F)	L.S.	1	1.00	75000	75000	7500	7,500.00	
9	Marshalling Box	No	1	1.00	900	900	90	90.00	
10	Earthing as per Sheet (E) 11 KV Bay	L.S.	1	1.00	11300	11300	1130	1,130.00	
11	MS Steel for RCC works etc	Job	1	1.00	7500	7500	750	750.00	
12	Metal Spreading 20 mm, 40 mm stone	M3	5	4.95	1000	4950	100	495.00	
13	Water arrangment if require	Job	1	1.00	1800	1800	180	180.00	
14	Miscellaneous materials for 11KV Bay i.e Gland, Lug, ferruler, PVC Pipe etc.	JOB	1	1.00	4300	4300	430	430.00	
Cost of material					140933.34	153550.02	14093.334	15355.002	

								100%	5%
11 KV FEEDER BAY with Gantry structure & PT 603 B									
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	5%	Total Amt (5%)	
1	L.As. 11 KV (Gapless type) with disconnector	Set	1	1.00	800	800	40	40	
2	11 KV Isolators with EB (800 A)	Set	1	1.00	9000	9000	450	450	
3	11 KV Isolators without EB (800 Amp.)	Set	1	1.00	9000	9000	450	450	
4	11 KV VCB 400 A Outdoor	Set	1	1.00	9000	9000	450	450	
5	11 KV PT	Set	3	3.00	2000	6000	100	300	
6	11 KV CT 400 - 200 / 5 - 5 Outdoor	No	3	3.00	2333.34	7000.02	116.667	350.001	
7	C&R Panel for 11 kv Outgoing Feeder OD	Nos.	1	1.00	7000	7000	350	350	
8	Structure and foundation cables, clamps, painting etc.as per sheet (A+B+C+D+F)	L.S.	1	1.00	75000	75000	3750	3750	
9	Marshalling Box	No	1	1.00	900	900	45	45	
10	Earthing as per Sheet (E) 11 KV Bay	L.S.	1	1.00	11300	11300	565	565	
11	MS Steel for RCC works etc	Job	1	1.00	7500	7500	375	375	
12	Metal Spreading 20 mm, 40 mm stone	M3	5	4.95	1000	4950	50	247.5	
13	Water arrangment if require	Job	1	1.00	1800	1800	90	90	
14	Miscellaneous materials for 11KV Bay i.e Gland, Lug, ferruler, PVC Pipe etc.	JOB	1	1.00	4300	4300	215	215	
Cost of material					140933.34	153550.02	7046.667	7677.501	

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory

							100%	85%	1.00
COST DATA FOR 11 kV SPECIAL DESIGNED TRANSFORMER									
Sr.No.	Description of Material	Unit	Qty	Total Qty	Rate	Amount	85%	Total Amt (85%)	
1	11 KV Specially Designed Transformer with all accessories, Control cable , Relays, contactors etc	Set	1	1.00	3,000.00	3,000.00	2,550.00	2,550.00	
2	11 KV Gang operated Three pole double Throw changeover switch	Set	1	1.00	2,300.00	2,300.00	1,955.00	1,955.00	
3	11 KV DP fabrication complete set with L.A.	Set	1	1.00	3,500.00	3,500.00	2,975.00	2,975.00	
4	16 Sqmm Single core multistrand copper Armoured Cable	Rmt.	15	15.00	25.00	375.00	21.25	318.75	
5	Relay Box MS fabricated with powder coating suitable for outdoor installation on of Relay.	No.	1	1.00	200.00	200.00	170.00	170.00	
6	Concreting ration 1:3 6	CMT	1.2	1.20	2,700.00	3,240.00	2,295.00	2,754.00	
7	CI Earthing 150mmDia & 3 Mtr Long	No.	2	2.00	3,000.00	6,000.00	2,550.00	5,100.00	
8	11 kV Pin Insulators with G.I. Pins	No.	3	3.00	15.00	45.00	12.75	38.25	
9	Disc Insulator 11 KV 70 KN	No.	6	6.00	30.00	180.00	25.50	153.00	
10	Strain Hardware for 55 Sq.mm AAAC	Set	6	6.00	20.00	120.00	17.00	102.00	
11	AAAC 55 mm2	Rmt	30	30.00	4.00	120.00	3.40	102.00	
12	Earthing Sets H.T	Set	2	2.00	170.00	340.00	144.50	289.00	
13	2Core 2.5sqmm Copper Cable	Rmt	20	20.00	15.00	300.00	12.75	255.00	
14	4 Core 2.5sqmm Copper Cable	Rmt	4	4.00	15.00	60.00	12.75	51.00	
15	RSJ 116x100, 9 m long	No.	2	2.00	2100.00	4200.00	1,785.00	3,570.00	
16	G.I.Wire 8 SWG/ 6 SWG	Kg.	15	15.00	2.00	30.00	1.70	25.50	
						24010.00	14531.60	20408.50	

						100%	10%	
COST DATA FOR 11 kV SPECIAL DESIGNED TRANSFORMER								
Sr.No.	Description of Material	Unit	Qty	Total Qty	Rate	Amount	10%	Total Amt (10%)
1	11 KV Specially Designed Transformer with all accessories, Control cable , Relays, contactors etc	Set	1	1.00	3,000.00	3,000.00	300.00	300.00
2	11 KV Gang operated Three pole double Throw changeover switch	Set	1	1.00	2,300.00	2,300.00	230.00	230.00
3	11 KV DP fabrication complete set with L.A.	Set	1	1.00	3,500.00	3,500.00	350.00	350.00
4	16 Sqmm Single core multistrand copper Armoured Cable	Rmt.	15	15.00	25.00	375.00	2.50	37.50
5	Relay Box MS fabricated with powder coating suitable for outdoor installation on of Relay.	No.	1	1.00	200.00	200.00	20.00	20.00
6	Concreting ration 1:3 6	CMT	1.2	1.20	2,700.00	3,240.00	270.00	324.00
7	CI Earthing 150mmDia & 3 Mtr Long	No.	2	2.00	3,000.00	6,000.00	300.00	600.00
8	11 kV Pin Insulators with G.I. Pins	No.	3	3.00	15.00	45.00	1.50	4.50
9	Disc Insulator 11 KV 70 KN	No.	6	6.00	30.00	180.00	3.00	18.00
10	Strain Hardware for 55 Sq.mm AAAC	Set	6	6.00	20.00	120.00	2.00	12.00
11	AAAC 55 mm2	Rmt	30	30.00	4.00	120.00	0.40	12.00
12	Earthing Sets H.T	Set	2	2.00	170.00	340.00	17.00	34.00
13	2Core 2.5sqmm Copper Cable	Rmt	20	20.00	15.00	300.00	1.50	30.00
14	4 Core 2.5sqmm Copper Cable	Rmt	4	4.00	15.00	60.00	1.50	6.00
15	RSJ 116x100, 9 m long	No.	2	2.00	2100.00	4200.00	210.00	420.00
16	G.I.Wire 8 SWG/ 6 SWG	Kg.	15	15.00	2.00	30.00	0.20	3.00
						24010.00	1709.60	2401.00

						100%	5%	
COST DATA FOR 11 kV SPECIAL DESIGNED TRANSFORMER								
Sr.No.	Description of Material	Unit	Qty	Total Qty	Rate	Amount	5%	Total Amt (5%)
1	11 KV Specially Designed Transformer with all accessories, Control cable , Relays, contactors etc	Set	1	1.00	3,000.00	3,000.00	150.00	150.00
2	11 KV Gang operated Three pole double Throw changeover switch	Set	1	1.00	2,300.00	2,300.00	115.00	115.00
3	11 KV DP fabrication complete set with L.A.	Set	1	1.00	3,500.00	3,500.00	175.00	175.00
4	16 Sqmm Single core multistrand copper Armoured Cable	Rmt.	15	15.00	25.00	375.00	1.25	18.75
5	Relay Box MS fabricated with powder coating suitable for outdoor installation on of Relay.	No.	1	1.00	200.00	200.00	10.00	10.00
6	Concreting ration 1:3 6	CMT	1.2	1.20	2,700.00	3,240.00	135.00	162.00
7	CI Earthing 150mmDia & 3 Mtr Long	No.	2	2.00	3,000.00	6,000.00	150.00	300.00
8	11 kV Pin Insulators with G.I. Pins	No.	3	3.00	15.00	45.00	0.75	2.25
9	Disc Insulator 11 KV 70 KN	No.	6	6.00	30.00	180.00	1.50	9.00
10	Strain Hardware for 55 Sq.mm AAAC	Set	6	6.00	20.00	120.00	1.00	6.00
11	AAAC 55 mm2	Rmt	30	30.00	4.00	120.00	0.20	6.00
12	Earthing Sets H.T	Set	2	2.00	170.00	340.00	8.50	17.00
13	2Core 2.5sqmm Copper Cable	Rmt	20	20.00	15.00	300.00	0.75	15.00
14	4 Core 2.5sqmm Copper Cable	Rmt	4	4.00	15.00	60.00	0.75	3.00
15	RSJ 116x100, 9 m long	No.	2	2.00	2100.00	4200.00	105.00	210.00
16	G.I.Wire 8 SWG/ 6 SWG	Kg.	15	15.00	2.00	30.00	0.10	1.50
						24010.00	854.80	1200.50

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory

						100%	85%	39.00
907-11 KV Single circuit Pin type with 55sq.mm AAAC lines on 100x116 mm 9 mtr RSJ poles								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	85%	Total Amt
1	RSJ 116x100, 9 m long	No.	15	585	2,100.00	31,500.00	1,785.00	10,44,225.00
2	RSJ 116x100, 8 m long	No.	2	78	1,500.00	3,000.00	1,275.00	99,450.00
3	11 kv Guarding channel MS 75x40 with clamp	Nos	4	156	500.00	2,000.00	425.00	66,300.00
4	Cut Point Set with Channel,angle and clamps	Set	4	156	1,250.00	5,000.00	1,062.50	1,65,750.00
5	11 KV V cross arm with clamp	No.	13	507	50.00	650.00	42.50	21,547.50
6	11 KV Top fitting with clamp	No.	17	663	20.00	340.00	17.00	11,271.00
7	G.I.Nut Bolts	Kg.	90	3510	3.00	270.00	2.55	8,950.50
8	11 kv Pin Insulators with G.I. Pins	No.	39	1521	15.00	585.00	12.75	19,392.75
9	Disc Insulator 11 KV 70 KN	No.	24	936	30.00	720.00	25.50	23,868.00
10	Strain Hardware for 55 Sq.mm AAAC	Set	24	936	20.00	480.00	17.00	15,912.00
11	AAAC 55 mm2	Rmt	3150	122850	6.00	18,900.00	5.10	6,26,535.00
12	Sleeve Joints	No.	3	117	10.00	30.00	8.50	994.50
13	H.T.Stay Set	Set	8	312	400.00	3,200.00	340.00	1,06,080.00
14	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	80	3120	5.00	400.00	4.25	13,260.00
15	Earthing Sets H.T	Set	17	663	170.00	2,890.00	144.50	95,803.50
16	G.I.Barbed Wire A' type.	Kg.	70	2730	10.00	700.00	8.50	23,205.00
17	Danger Board in yard.	No.	17	663	5.00	85.00	4.25	2,817.75
18	Concreting ration 1:3 6 (14 CMT)	Cmt.	15	585	2,700.00	40,500.00	2,295.00	13,42,575.00
19	G.I.Wire 8 SWG/ 6 SWG	Kg.	130	5070	2.00	260.00	1.70	8,619.00
20	Black Bituminus Paint	Ltr	6	234	10.00	60.00	8.50	1,989.00
21	Red Oxide Paint for 1 coats	Ltr	20	780	14.00	280.00	11.90	9,282.00
22	Aluminium Paint for 1 coat	Ltr	9	351	10.00	90.00	8.50	2,983.50
23	Wedge connectors RABIT To RABIT or equivalent AAAC	Nos	12	468	5.00	60.00	4.25	1,989.00
24	RSJ 116x100, 11 m long	No.	1	39	2,500.00	2,500.00	2,125.00	82,875.00
25	RSJ 116x100, 10 m long	No.	1	39	2,100.00	2,100.00	1,785.00	69,615.00
						1,16,600.00	11,419.75	38,65,290.00

						100%	10%	
907-11 KV Single circuit Pin type with 55sq.mm AAAC lines on 100x116 mm 9 mtr RSJ poles								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	10%	Total Amt (10%)
1	RSJ 116x100, 9 m long	No.	15	585	2,100.00	31,500.00	210.00	1,22,850.00
2	RSJ 116x100, 8 m long	No.	2	78	1,500.00	3,000.00	150.00	11,700.00
3	11 kv Guarding channel MS 75x40 with clamp	Nos	4	156	500.00	2,000.00	50.00	7,800.00
4	Cut Point Set with Channel,angle and clamps	Set	4	156	1,250.00	5,000.00	125.00	19,500.00
5	11 KV V cross arm with clamp	No.	13	507	50.00	650.00	5.00	2,535.00
6	11 KV Top fitting with clamp	No.	17	663	20.00	340.00	2.00	1,326.00
7	G.I.Nut Bolts	Kg.	90	3510	3.00	270.00	0.30	1,053.00
8	11 kv Pin Insulators with G.I. Pins	No.	39	1521	15.00	585.00	1.50	2,281.50
9	Disc Insulator 11 KV 70 KN	No.	24	936	30.00	720.00	3.00	2,808.00
10	Strain Hardware for 55 Sq.mm AAAC	Set	24	936	20.00	480.00	2.00	1,872.00
11	AAAC 55 mm2	Rmt	3150	122850	6.00	18,900.00	0.60	73,710.00
12	Sleeve Joints	No.	3	117	10.00	30.00	1.00	117.00
13	H.T.Stay Set	Set	8	312	400.00	3,200.00	40.00	12,480.00
14	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	80	3120	5.00	400.00	0.50	1,560.00
15	Earthing Sets H.T	Set	17	663	170.00	2,890.00	17.00	11,271.00
16	G.I.Barbed Wire A' type.	Kg.	70	2730	10.00	700.00	1.00	2,730.00
17	Danger Board in yard.	No.	17	663	5.00	85.00	0.50	331.50
18	Concreting ration 1:3 6 (14 CMT)	Cmt.	15	585	2,700.00	40,500.00	270.00	1,57,950.00
19	G.I.Wire 8 SWG/ 6 SWG	Kg.	130	5070	2.00	260.00	0.20	1,014.00
20	Black Bituminus Paint	Ltr	6	234	10.00	60.00	1.00	234.00
21	Red Oxide Paint for 1 coats	Ltr	20	780	14.00	280.00	1.40	1,092.00
22	Aluminium Paint for 1 coat	Ltr	9	351	10.00	90.00	1.00	351.00
23	Wedge connectors RABIT To RABIT or equivalent AAAC	Nos	12	468	5.00	60.00	0.50	234.00
24	RSJ 116x100, 11 m long	No.	1	39	2,500.00	2,500.00	250.00	9,750.00
25	RSJ 116x100, 10 m long	No.	1	39	2,100.00	2,100.00	210.00	8,190.00
						1,16,600.00	1,343.50	4,54,740.00

						100%	5%	
907-11 KV Single circuit Pin type with 55sq.mm AAAC lines on 100x116 mm 9 mtr RSJ poles								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	5%	Total Amt
1	RSJ 116x100, 9 m long	No.	15	585	2,100.00	31,500.00	105.00	61,425.00
2	RSJ 116x100, 8 m long	No.	2	78	1,500.00	3,000.00	75.00	5,850.00
3	11 kv Guarding channel MS 75x40 with clamp	Nos	4	156	500.00	2,000.00	25.00	3,900.00
4	Cut Point Set with Channel,angle and clamps	Set	4	156	1,250.00	5,000.00	62.50	9,750.00
5	11 KV V cross arm with clamp	No.	13	507	50.00	650.00	2.50	1,267.50
6	11 KV Top fitting with clamp	No.	17	663	20.00	340.00	1.00	663.00
7	G.I.Nut Bolts	Kg.	90	3510	3.00	270.00	0.15	526.50
8	11 kv Pin Insulators with G.I. Pins	No.	39	1521	15.00	585.00	0.75	1,140.75
9	Disc Insulator 11 KV 70 KN	No.	24	936	30.00	720.00	1.50	1,404.00
10	Strain Hardware for 55 Sq.mm AAAC	Set	24	936	20.00	480.00	1.00	936.00
11	AAAC 55 mm2	Rmt	3150	122850	6.00	18,900.00	0.30	36,855.00
12	Sleeve Joints	No.	3	117	10.00	30.00	0.50	58.50
13	H.T.Stay Set	Set	8	312	400.00	3,200.00	20.00	6,240.00
14	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	80	3120	5.00	400.00	0.25	780.00
15	Earthing Sets H.T	Set	17	663	170.00	2,890.00	8.50	5,635.50
16	G.I.Barbed Wire A' type.	Kg.	70	2730	10.00	700.00	0.50	1,365.00
17	Danger Board in yard.	No.	17	663	5.00	85.00	0.25	165.75
18	Concreting ration 1:3 6 (14 CMT)	Cmt.	15	585	2,700.00	40,500.00	135.00	78,975.00
19	G.I.Wire 8 SWG/ 6 SWG	Kg.	130	5070	2.00	260.00	0.10	507.00
20	Black Bituminus Paint	Ltr	6	234	10.00	60.00	0.50	117.00
21	Red Oxide Paint for 1 coats	Ltr	20	780	14.00	280.00	0.70	546.00
22	Aluminium Paint for 1 coat	Ltr	9	351	10.00	90.00	0.50	175.50
23	Wedge connectors RABIT To RABIT or equivalent AAAC	Nos	12	468	5.00	60.00	0.25	117.00
24	RSJ 116x100, 11 m long	No.	1	39	2,500.00	2,500.00	125.00	4,875.00
25	RSJ 116x100, 10 m long	No.	1	39	2,100.00	2,100.00	105.00	4,095.00
						1,16,600.00	671.75	2,27,370.00

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory

							100%	85%	
916 - laying of 1 Km. 11 KV 3 C 95 mm 2 XLPE under ground Cable									
Sr. No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	85%	Total Amt (85%)	
1	Laying and Excavation of XLPE Cable 11 KV, 3 C / 95 mm sq.	mtr	1000.00	0.00	225.00	225000.00	191.25	0	
2	R.C.C. Pipe 150 mm 2 M	No	30.00	0.00	10.00	300.00	8.5	0	
3	Half round cement pipe (150mm X 1mtr)	No.	940.00	0.00	10.00	9400.00	8.5	0	
4	11 kV heat shrinkable Straight through joint kit for 3 C X 95	No.	2.00	0.00	2200.00	4400.00	1870	0	
5	11 kV heat shrinkable Outdoor termination joint kit for 3 C X 95	No.	2.00	0.00	2000.00	4000.00	1700	0	
6	Sand	Cmt	2.50	0.00	2000.00	5000.00	1700	0	
7	Misc. for XLPE U/G Cable	LS	1.00	0.00	1900.00	1900.00	1615	0	
						250000.00	7093.25	0	

							100%	10%	
916 - laying of 1 Km. 11 KV 3 C 95 mm 2 XLPE under ground Cable									
Sr. No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	10%	Total Amt (10%)	
1	Laying and Excavation of XLPE Cable 11 KV, 3 C / 95 mm sq.	mtr	1000.00	0.00	225.00	225000.00	22.5	0	
2	R.C.C. Pipe 150 mm 2 M	No	30.00	0.00	10.00	300.00	1	0	
3	Half round cement pipe (150mm X 1mtr)	No.	940.00	0.00	10.00	9400.00	1	0	
4	11 kV heat shrinkable Straight through joint kit for 3 C X 95	No.	2.00	0.00	2200.00	4400.00	220	0	
5	11 kV heat shrinkable Outdoor termination joint kit for 3 C X 95	No.	2.00	0.00	2000.00	4000.00	200	0	
6	Sand	Cmt	2.50	0.00	2000.00	5000.00	200	0	
7	Misc. for XLPE U/G Cable	LS	1.00	0.00	1900.00	1900.00	190	0	
						250000.00	834.5	0	

							100%	5%	
916 - laying of 1 Km. 11 KV 3 C 95 mm 2 XLPE under ground Cable									
Sr. No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	5%	Total Amt (5%)	
1	Laying and Excavation of XLPE Cable 11 KV, 3 C / 95 mm sq.	mtr	1000.00	0.00	225.00	225000.00	11.25	0	
2	R.C.C. Pipe 150 mm 2 M	No	30.00	0.00	10.00	300.00	0.5	0	
3	Half round cement pipe (150mm X 1mtr)	No.	940.00	0.00	10.00	9400.00	0.5	0	
4	11 kV heat shrinkable Straight through joint kit for 3 C X 95	No.	2.00	0.00	2200.00	4400.00	110	0	
5	11 kV heat shrinkable Outdoor termination joint kit for 3 C X 95	No.	2.00	0.00	2000.00	4000.00	100	0	
6	Sand	Cmt	2.50	0.00	2000.00	5000.00	100	0	
7	Misc. for XLPE U/G Cable	LS	1.00	0.00	1900.00	1900.00	95	0	
						250000.00	417.25	0	

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory

						100%	85%	-
data for11 KV Single circuit Pin type with AB cable 3Cx95+70 sqmm on 100x116 mm 10 mtr RSJ p								
Sr. No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	85%	Total Amt (85%)
1	RSJ 116x100, 10 m long	No.	19	0	2,100.00	39,900.00	1785.00	0
2	RSJ 116x100, 9 m long	No.	4	0	2,100.00	8,400.00	1785.00	0
3	Cut Point Set with Channel,angle and clamps	Set	6	0	750.00	4,500.00	637.50	0
4	11 KV V cross arm with clamp	No.	13	0	50.00	650.00	42.50	0
5	11 KV Top fitting with clamp	No.	13	0	20.00	260.00	17.00	0
6	G.I.Nut Bolts	Kg.	90	0	3.00	270.00	2.55	0
7	11 kV Pin Insulators with G.I. Pins	No.	39	0	15.00	585.00	12.75	0
8	Disc Insulator 11 KV 70 KN	No.	36	0	30.00	1,080.00	25.50	0
9	Strain Hardware for 55 Sq.mm AAAC	Set	36	0	20.00	720.00	17.00	0
10	11 kV HT Covered Conductor	Rmt	3000	0	1.50	4,500.00	1.28	0
11	Sleve Joints	No.	3	0	10.00	30.00	8.50	0
12	H.T.Stay Set	Set	8	0	400.00	3,200.00	340.00	0
13	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	80	0	5.00	400.00	4.25	0
14	Earthing Sets H.T	Set	19	0	170.00	3,230.00	144.50	0
15	G.I.Barbed Wire A' type.	Kg.	77	0	10.00	770.00	8.50	0
16	Danger Board in yard.	No.	19	0	5.00	95.00	4.25	0
17	Concreting ration 1:3 6	Cmt.	15.133	0	2,700.00	40,860.18	2295.00	0
18	G.I.Wire 8 SWG/ 6 SWG	Kg.	38	0	2.20	83.60	1.87	0
19	Black Bituminus Paint	LTR	6	0	10.00	60.00	8.50	0
20	Red Oxide Paint for 1 coats	LTR	22	0	14.00	308.00	11.90	0
21	Aluminium Paint for 1 coat	LTR	10	0	10.00	99.00	8.50	0
22	Sundries	Ls	1	0	-	-	0.00	0
23	Wedge connectors			0	5.00		4.25	0
a)	DOG TO DOG or equivalent AAAC	No	0	0	3.00	-	2.55	0
						110000.78	7168.65	0.00

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory

						100%	10%	
Cost data for 11 KV Single circuit Pin type with AB cable 3Cx95+70 sqmm on 100x116 mm 10 mtr RSJ poles								
Sr. No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	10%	Total Amt (10%)
1	RSJ 116x100, 10 m long	No.	19	0	2,100.00	39,900.00	210.00	-
2	RSJ 116x100, 9 m long	No.	4	0	2,100.00	8,400.00	210.00	-
3	Cut Point Set with Channel, angle and clamps	Set	6	0	750.00	4,500.00	75.00	-
4	11 KV V cross arm with clamp	No.	13	0	50.00	650.00	5.00	-
5	11 KV Top fitting with clamp	No.	13	0	20.00	260.00	2.00	-
6	G.I. Nut Bolts	Kg.	90	0	3.00	270.00	0.30	-
7	11 kV Pin Insulators with G.I. Pins	No.	39	0	15.00	585.00	1.50	-
8	Disc Insulator 11 KV 70 KN	No.	36	0	30.00	1,080.00	3.00	-
9	Strain Hardware for 55 Sq.mm AAAC	Set	36	0	20.00	720.00	2.00	-
10	11 kV HT Covered Conductor	Rmt	3000	0	1.50	4,500.00	0.15	-
11	Sleeve Joints	No.	3	0	10.00	30.00	1.00	-
12	H.T. Stay Set	Set	8	0	400.00	3,200.00	40.00	-
13	G.I. Stay Wire 7/4mm (8 SWG)	Kg.	80	0	5.00	400.00	0.50	-
14	Earthing Sets H.T	Set	19	0	170.00	3,230.00	17.00	-
15	G.I. Barbed Wire A' type.	Kg.	77	0	10.00	770.00	1.00	-
16	Danger Board in yard.	No.	19	0	5.00	95.00	0.50	-
17	Concreting ration 1:3:6	Cmt.	15.133	0	2,700.00	40,860.18	270.00	-
18	G.I. Wire 8 SWG/ 6 SWG	Kg.	38	0	2.20	83.60	0.22	-
19	Black Bituminous Paint	LTR	6	0	10.00	60.00	1.00	-
20	Red Oxide Paint for 1 coats	LTR	22	0	14.00	308.00	1.40	-
21	Aluminium Paint for 1 coat	LTR	10	0	10.00	99.00	1.00	-
22	Wedge connectors			0	5.00		0.50	-
a)	DOG TO DOG or equivalent AAAC	No	0	0	3.00	-	0.30	-
						110000.78	843.37	-

						100%	5%	
Cost data for 11 KV Single circuit Pin type with AB cable 3Cx95+70 sqmm on 100x116 mm 10 mtr RSJ poles								
Sr. No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	5%	Total Amt (5%)
1	RSJ 116x100, 10 m long	No.	19	0	2,100.00	39,900.00	105.00	-
2	RSJ 116x100, 9 m long	No.	4	0	2,100.00	8,400.00	105.00	-
3	Cut Point Set with Channel, angle and clamps	Set	6	0	750.00	4,500.00	37.50	-
4	11 KV V cross arm with clamp	No.	13	0	50.00	650.00	2.50	-
5	11 KV Top fitting with clamp	No.	13	0	20.00	260.00	1.00	-
6	G.I. Nut Bolts	Kg.	90	0	3.00	270.00	0.15	-
7	11 kV Pin Insulators with G.I. Pins	No.	39	0	15.00	585.00	0.75	-
8	Disc Insulator 11 KV 70 KN	No.	36	0	30.00	1,080.00	1.50	-
9	Strain Hardware for 55 Sq.mm AAAC	Set	36	0	20.00	720.00	1.00	-
10	11 kV HT Covered Conductor	Rmt	3000	0	1.50	4,500.00	0.08	-
11	Sleeve Joints	No.	3	0	10.00	30.00	0.50	-
12	H.T. Stay Set	Set	8	0	400.00	3,200.00	20.00	-
13	G.I. Stay Wire 7/4mm(8 SWG)	Kg.	80	0	5.00	400.00	0.25	-
14	Earthing Sets H.T	Set	19	0	170.00	3,230.00	8.50	-
15	G.I. Barbed Wire A' type.	Kg.	77	0	10.00	770.00	0.50	-
16	Danger Board in yard.	No.	19	0	5.00	95.00	0.25	-
17	Concreting ration 1:3 6	Cmt.	15.133	0	2,700.00	40,860.18	135.00	-
18	G.I. Wire 8 SWG/ 6 SWG	Kg.	38	0	2.20	83.60	0.11	-
19	Black Bituminous Paint	LTR	6	0	10.00	60.00	0.50	-
20	Red Oxide Paint for 1 coats	LTR	22	0	14.00	308.00	0.70	-
21	Aluminium Paint for 1 coat	LTR	10	0	10.00	99.00	0.50	-
22	Sundries	Ls	1	0	-	-	0.00	-
23	Wedge connectors			0	5.00		0.25	-
a)	DOG TO DOG or equivalent AAAC	No	0	0	3.00	-	0.15	-
						110000.78	421.69	-

19.00

							100%	85%
1220- 100 KVA Dist. Transformer centers on RSJ , 100 X 116 mm, 11 mtr with Kitkat Dist box.								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	85%	Total Amt (85%)
1	Dist. Transformer 100 KVA 11/0.43 kv	No	1	19	3000.00	3000.00	2550	48450
2	RSJ 116x100, 11 m long	No	2	38	2500.00	5000.00	2125	80750
3	Top & Bottom MS Channel (100x50x6 mm)	No	4	76	250.00	1000.00	212.5	16150
4	AB Switch, HG Fuse, LTDB Channel (75x40x6 mm) with Support Angle	No	6	114	250.00	1500.00	212.5	24225
5	M.S.Flat 50 x 6 mm for Stay and Back Clamp	No	32	608	12.00	384.00	10.2	6201.6
6	11 kv Pin Insulators with G.I. Pins	No	3	57	15.00	45.00	12.75	726.75
7	L.T.Dist.Boxes 100 KVA vuth KITKAT	No	1	19	900.00	900.00	765	14535
8	L.As. 11 KV (Gapless type) with disconnector	Set	1	19	800.00	800.00	680	12920
9	H.T.Stay Set	Set	1	19	400.00	400.00	340	6460
10	Earthing Sets H.T	Set	5	95	285.00	1425.00	242.25	23013.75
11	11KV H.G.Fuses	Set	1	19	900.00	900.00	765	14535
12	11KV A.B. Switch, 400 A	Set	1	19	1800.00	1800.00	1530	29070
13	Danger Board in yard.	No	2	38	10.00	20.00	8.5	323
14	Painting/H ardware & support with numbering of pole	LS	1.04	20	25.00	26.00	21.25	419.9
15	DTC Metring Cth Box, single core L.T. XLPE cable (70 sq.mm. 120 mtr length) and other allied material.	No	1	19	1600.00	1600.00	1360	25840
17	Concreting ration 1:3 6	CMT	1.60	30	2700.00	4320.00	2295	69768
18	GI STAY WIRE (7X4MM DIA)	Kg.	9.0	171	3.00	27.00	2.55	436.05
19	G.I. Barbed Wire	Kg.	10.0	190	5.00	50.00	4.25	807.5
20	BSWG GI WIRE FOR EARTHING & GUARDING	Kg.	25.0	475	2.00	50.00	1.7	807.5
21	G.I.Nut Bolts	Kg.	10.0	190	3.00	30.00	2.55	484.5
22	Disc Insulator 11 KV 70 KN	No.	3.0	57	30.00	90.00	25.5	1453.5
23	Strain Hardware for 55 Sq.mm AAAC	No.	3.0	57	20.00	60.00	17	969
24	AAAC 55 mm2	Rmt	15.0	285	6.00	90.00	5.1	1453.5
						23517.00	13188.6	379799.55

							100%	10%
1220- 100 KVA Dist. Transformer centers on RSJ , 100 X 116 mm, 11 mtr with Kitkat Dist box.								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	10%	Total Amt (10%)
1	Dist. Transformer 100 KVA 11/0.43 kv	No	1	19	3000.00	3000.00	300	5700
2	RSJ 116x100, 11 m long	No	2	38	2500.00	5000.00	250	9500
3	Top & Bottom MS Channel (100x50x6 mm)	No	4	76	250.00	1000.00	25	1900
4	AB Switch, HG Fuse, LTDB Channel (75x40x6 mm) with Support Angle	No	6	114	250.00	1500.00	25	2850
5	M.S.Flat 50 x 6 mm for Stay and Back Clamp	No	32	608	12.00	384.00	1.2	729.6
6	11 kv Pin Insulators with G.I. Pins	No	3	57	15.00	45.00	1.5	85.5
7	L.T.Dist.Boxes 100 KVA vuth KITKAT	No	1	19	900.00	900.00	90	1710
8	L.As. 11 KV (Gapless type) with disconnector	Set	1	19	800.00	800.00	80	1520
9	H.T.Stay Set	Set	1	19	400.00	400.00	40	760
10	Earthing Sets H.T	Set	5	95	285.00	1425.00	28.5	2707.5
11	11KV H.G.Fuses	Set	1	19	900.00	900.00	90	1710
12	11KV A.B. Switch, 400 A	Set	1	19	1800.00	1800.00	180	3420
13	Danger Board in yard.	No	2	38	10.00	20.00	1	38
14	Painting/H ardware & support with numbering of pole	LS	1.04	20	25.00	26.00	2.5	49.4
15	DTC Metring Cth Box, single core L.T. XLPE cable (70 sq.mm. 120 mtr length) and other allied material.	No	1	19	1600.00	1600.00	160	3040
17	Concreting ration 1:3 6	CMT	1.60	30	2700.00	4320.00	270	8208
18	GI STAY WIRE (7X4MM DIA)	Kg.	9.0	171	3.00	27.00	0.3	51.3
19	G.I. Barbed Wire	Kg.	10.0	190	5.00	50.00	0.5	95
20	BSWG GI WIRE FOR EARTHING & GUARDING	Kg.	25.0	475	2.00	50.00	0.2	95
21	G.I.Nut Bolts	Kg.	10.0	190	3.00	30.00	0.3	57
22	Disc Insulator 11 KV 70 KN	No.	3.0	57	30.00	90.00	3	171
23	Strain Hardware for 55 Sq.mm AAAC	No.	3.0	57	20.00	60.00	2	114
24	AAAC 55 mm2	Rmt	15.0	285	6.00	90.00	0.6	171
						23517.00	1551.6	44682.3

							100%	5%
1220- 100 KVA Dist. Transformer centers on RSJ , 100 X 116 mm, 11 mtr with Kitkat Dist box.								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	5%	Total Amt (5%)
1	Dist. Transformer 100 KVA 11/0.43 kv	No	1	19	3000.00	3000.00	150	2850
2	RSJ 116x100, 11 m long	No	2	38	2500.00	5000.00	125	4750
3	Top & Bottom MS Channel (100x50x6 mm)	No	4	76	250.00	1000.00	12.5	950
4	AB Switch, HG Fuse, LTDB Channel (75x40x6 mm) with Support Angle	No	6	114	250.00	1500.00	12.5	1425
5	M.S.Flat 50 x 6 mm for Stay and Back Clamp	No	32	608	12.00	384.00	0.6	364.8
6	11 kv Pin Insulators with G.I. Pins	No	3	57	15.00	45.00	0.75	42.75
7	L.T.Dist.Boxes 100 KVA vuth KITKAT	No	1	19	900.00	900.00	45	855
8	L.As. 11 KV (Gapless type) with disconnector	Set	1	19	800.00	800.00	40	760
9	H.T.Stay Set	Set	1	19	400.00	400.00	20	380
10	Earthing Sets H.T	Set	5	95	285.00	1425.00	14.25	1353.75
11	11KV H.G.Fuses	Set	1	19	900.00	900.00	45	855
12	11KV A.B. Switch, 400 A	Set	1	19	1800.00	1800.00	90	1710
13	Danger Board in yard.	No	2	38	10.00	20.00	0.5	19
14	Painting/H ardware & support with numbering of pole	LS	1.04	20	25.00	26.00	1.25	24.7
15	DTC Metring Cth Box, single core L.T. XLPE cable (70 sq.mm. 120 mtr length) and other allied material.	No	1	19	1600.00	1600.00	80	1520
17	Concreting ration 1:3 6	CMT	1.60	30	2700.00	4320.00	135	4104
18	GI STAY WIRE (7X4MM DIA)	Kg.	9.0	171	3.00	27.00	0.15	25.65
19	G.I. Barbed Wire	Kg.	10.0	190	5.00	50.00	0.25	47.5
20	BSWG GI WIRE FOR EARTHING & GUARDING	Kg.	25.0	475	2.00	50.00	0.1	47.5
21	G.I.Nut Bolts	Kg.	10.0	190	3.00	30.00	0.15	28.5
22	Disc Insulator 11 KV 70 KN	No.	3.0	57	30.00	90.00	1.5	85.5
23	Strain Hardware for 55 Sq.mm AAAC	No.	3.0	57	20.00	60.00	1	57
24	AAAC 55 mm2	Rmt	15.0	285	6.00	90.00	0.3	85.5
						23517.00	775.8	22341.15

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory

						100%	85%	10.00
3 phase 5 wire LT line with AAAC 55 sqmm for phase and ACSR Weasel for neutral on PSC pole, 8 mtr.140 Kg								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	85%	Total Amt (85%)
1	PSC Pole 8 Mtr (140 KG)	No	20	200	1000.00	20000.00	850	170000
2	AAAC 55 mm2	Rmt	3100	31000	3.00	9300.00	2.55	79050
3	ACSR Weasel	Rmt	2100	21000	2.00	4200.00	1.7	35700
4	M5 angle 50x50x6 mm for LT Bracket	No	4	40	90.00	360.00	76.5	3060
5	M.S. Flats(50 X 10mm) for Clamps	Nos	20	200	12.00	240.00	10.2	2040
6	L.T.Shackle Insulator	No	70	700	6.00	420.00	5.1	3570
7	Aluminium Bobbins for neutral	No.	24	240	2.00	48.00	1.7	408
8	L.T.Shackle hardware	Pair	120	1200	3.00	360.00	2.55	3060
9	Jointing Sleeves for AAC	No	5	50	5.00	25.00	4.25	212.5
10	PG Clamp	No	6	60	8.00	48.00	6.8	408
11	Earthing Sets L.T.	Set	5	50	285.00	1425.00	242.25	12112.5
12	L.T. Stay sets	Set	8	80	400.00	3200.00	340	27200
13	G.I.Stay Wire 7/3.15mm(10SWG)	Kg.	56	560	8.00	448.00	6.8	3808
14	Stay Insulators	No	8	80	4.00	32.00	3.4	272
15	Binding Wire	Kg	1.80	18	2.50	4.50	2.125	38.25
16	Binding Tape	Kg	1.80	18	2.50	4.50	2.125	38.25
17	G.I.Wire 8 SWG/ 6 SWG	Kg.	40	400	4.00	160.00	3.4	1360
18	L.T.Spacers	No	35	350	12.00	420.00	10.2	3570
19	G.I.N ut Bolts	Kg	57	570	3.00	171.00	2.55	1453.5
a)	Ant To Ant or equivalent AAAC	No	32	320	3.00	96.00	2.55	816
b)	GNAT To GNAT or equivalent AAAC	No	24	240	2.00	48.00	1.7	408
20	Sundries	LS	1	10		0.00	0	0
21	Concreting ration 1:3 6	CMT	0	0	2700.00	0.00	2295	0
Cost of Material						41010.00	3873.45	348585

						100%	10%	
3 phase 5 wire LT line with AAAC 55 sqmm for phase and ACSR Weasel for neutral on PSC pole, 8 mtr.140 Kg								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	10%	Total Amt (10%)
1	PSC Pole 8 Mtr (140 KG)	No	20	200	1000.00	20000.00	100	20000
2	AAAC 55 mm2	Rmt	3100	31000	3.00	9300.00	0.3	9300
3	ACSR Weasel	Rmt	2100	21000	2.00	4200.00	0.2	4200
4	MS angle 50x50x6 mm for LT Bracket	No	4	40	90.00	360.00	9	360
5	M.S. Flats(50 X 10mm) for Clamps	Nos	20	200	12.00	240.00	1.2	240
6	L.T.Shackle Insulator	No	70	700	6.00	420.00	0.6	420
7	Aluminium Bobbins for neutral	No.	24	240	2.00	48.00	0.2	48
8	L.T.Shackle hardware	Pair	120	1200	3.00	360.00	0.3	360
9	Jointing Sleeves for AAC	No	5	50	5.00	25.00	0.5	25
10	PG Clamp	No	6	60	8.00	48.00	0.8	48
11	Earthing Sets L.T.	Set	5	50	285.00	1425.00	28.5	1425
12	L.T. Stay sets	Set	8	80	400.00	3200.00	40	3200
13	G.I.Stay Wire 7/3.15mm(10SWG)	Kg.	56	560	8.00	448.00	0.8	448
14	Stay Insulators	No	8	80	4.00	32.00	0.4	32
15	Binding Wire	Kg	1.80	18	2.50	4.50	0.25	4.5
16	Binding Tape	Kg	1.80	18	2.50	4.50	0.25	4.5
17	G.I.Wire 8 SWG/ 6 SWG	Kg.	40	400	4.00	160.00	0.4	160
18	L.T.Spacers	No	35	350	12.00	420.00	1.2	420
19	G.I.N ut Bolts	Kg	57	570	3.00	171.00	0.3	171
a)	Ant To Ant or equivalent AAAC	No	32	320	3.00	96.00	0.3	96
b)	GNAT To GNAT or equivalent AAAC	No	24	240	2.00	48.00	0.2	48
20	Sundries	LS	1	10		0.00	0	0
21	Concreting ration 1:3 6	CMT	0	0	2700.00	0.00	270	0
Cost of Material						41010.00	455.7	41010

						100%	5%	
3 phase 5 wire LT line with AAAC 55 sqmm for phase and ACSR Weasel for neutral on PSC pole, 8 mtr.140 Kg								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	5%	Total Amt (5%)
1	PSC Pole 8 Mtr (140 KG)	No	20	200	1000.00	20000.00	50	10000
2	AAAC 55 mm2	Rmt	3100	31000	3.00	9300.00	0.15	4650
3	ACSR Weasel	Rmt	2100	21000	2.00	4200.00	0.1	2100
4	MS angle 50x50x6 mm for LT Bracket	No	4	40	90.00	360.00	4.5	180
5	M.S. Flats(50 X 10mm) for Clamps	Nos	20	200	12.00	240.00	0.6	120
6	L.T.Shackle Insulator	No	70	700	6.00	420.00	0.3	210
7	Aluminium Bobbins for neutral	No.	24	240	2.00	48.00	0.1	24
8	L.T.Shackle hardware	Pair	120	1200	3.00	360.00	0.15	180
9	Jointing Sleeves for AAC	No	5	50	5.00	25.00	0.25	12.5
10	PG Clamp	No	6	60	8.00	48.00	0.4	24
11	Earthing Sets L.T.	Set	5	50	285.00	1425.00	14.25	712.5
12	L.T. Stay sets	Set	8	80	400.00	3200.00	20	1600
13	G.I.Stay Wire 7/3.15mm(10SWG)	Kg.	56	560	8.00	448.00	0.4	224
14	Stay Insulators	No	8	80	4.00	32.00	0.2	16
15	Binding Wire	Kg	1.80	18	2.50	4.50	0.125	2.25
16	Binding Tape	Kg	1.80	18	2.50	4.50	0.125	2.25
17	G.I.Wire 8 SWG/ 6 SWG	Kg.	40	400	4.00	160.00	0.2	80
18	L.T.Spacers	No	35	350	12.00	420.00	0.6	210
19	G.I.N ut Bolts	Kg	57	570	3.00	171.00	0.15	85.5
a)	Ant To Ant or equivalent AAAC	No	32	320	3.00	96.00	0.15	48
b)	GNAT To GNAT or equivalent AAAC	No	24	240	2.00	48.00	0.1	24
20	Sundries	LS	1	10		0.00	0	0
21	Concreting ration 1:3 6	CMT	0	0	2700.00	0.00	135	0
Cost of Material						41010.00	227.85	20505

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory



7.00

						100%	85%	
11 kV A.B. Switch 400 Amp with DP structure.								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	85%	Total Amt (85%)
1	11KV A.B. Swtch, 400 A	Set	1	7	1800.00	1800.00	1530	10710
2	MS Channel Top Channel (100x50x6 mm)	No	2	14	125.00	250.00	106.25	1487.5
3	M.S.Channel AB switch (75x40x6 mm)	No	2	14	125.00	250.00	106.25	1487.5
4	H.T.Stay Set	Set	2	14	600.00	1200.00	510	7140
5	Strain Hardware forWeasel/Squirrel	Set	6	42	10.00	60.00	8.5	357
6	Disc Insulator 11 KV 70 KN	No	6	42	35.00	210.00	29.75	1249.5
7	RSJ 116x100, 9 m long	No	2	14	2100.00	4200.00	1785	24990
8	Concreting ration 1:3 6	CMT	1.308	9	2700.00	3530.25	2295	21004.9875
	Cost of Material					11500.25	6370.75	68426.4875

						100%	10%	
11 kV A.B. Switch 400 Amp with DP structure.								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	10%	Total Amt (10%)
1	11KV A.B. Swtch, 400 A	Set	1	7	1800.00	1800.00	180	1260
2	MS Channel Top Channel (100x50x6 mm)	No	2	14	125.00	250.00	12.5	175
3	M.S.Channel AB switch (75x40x6 mm)	No	2	14	125.00	250.00	12.5	175
4	H.T.Stay Set	Set	2	14	600.00	1200.00	60	840
5	Strain Hardware forWeasel/Squirrel	Set	6	42	10.00	60.00	1	42
6	Disc Insulator 11 KV 70 KN	No	6	42	35.00	210.00	3.5	147
7	RSJ 116x100, 9 m long	No	2	14	2100.00	4200.00	210	2940
8	Concreting ration 1:3 6	CMT	1.308	9	2700.00	3530.25	270	2471.175
	Cost of Material					11500.25	749.5	8050.175

						100%	5%	
11 kV A.B. Switch 400 Amp with DP structure.								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	5%	Total Amt (5%)
1	11KV A.B. Swtch, 400 A	Set	1	7	1800.00	1800.00	90	630
2	MS Channel Top Channel (100x50x6 mm)	No	2	14	125.00	250.00	6.25	87.5
3	M.S.Channel AB switch (75x40x6 mm)	No	2	14	125.00	250.00	6.25	87.5
4	H.T.Stay Set	Set	2	14	600.00	1200.00	30	420
5	Strain Hardware forWeasel/Squirrel	Set	6	42	10.00	60.00	0.5	21
6	Disc Insulator 11 KV 70 KN	No	6	42	35.00	210.00	1.75	73.5
7	RSJ 116x100, 9 m long	No	2	14	2100.00	4200.00	105	1470
8	Concreting ration 1:3 6	CMT	1.308	9	2700.00	3530.25	135	1235.5875
	Cost of Material					11500.25	374.75	4025.0875

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory

-

						100%	85%	
SINGLE POLE CUT POINT STRUCTURE FOR 11KV LINE ON RSJ 11 M POLE (Act-No 924)								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	85%	Total Amt (85%)
1	RSJ 152x152, 11 m long	No.	1	0	3150.00	3150.00	2677.5	0
2	M.S.Cut Point Channel with complete set	set	1	0	650.00	650.00	552.5	0
3	Strain Hardware for Dog0.1 or Equ.AAAC.	No.	6	0	20.00	120.00	17	0
4	Disc Insulator 11 KV 70 KN	No.	6	0	30.00	180.00	25.5	0
5	H.T.Stay Set	No.	2	0	400.00	800.00	340	0
6	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	13	0	5.00	65.00	4.25	0
7	Earthing Sets H.T	No.	1	0	285.00	285.00	242.25	0
8	G.I.Wire 8 SWG/ 6 SWG	Kg.	2	0	4.00	8.00	3.4	0
9	G.I.Barbed Wire A' type.	Kg.	2	0	3.00	6.00	2.55	0
10	Black Bituminus Paint	Ltr.	0.5	0	10.00	5.00	8.5	0
11	Red Oxide Paint for 1 coats	Ltr.	1	0	14.00	14.00	11.9	0
12	Aluminium Paint for 1 coat	Ltr.	1	0	14.00	14.00	11.9	0
13	Danger Board in yard.	No.	1	0	10.00	10.00	8.5	0
14	Concreting ration 1:3 6	Cmt.	0.812	0	2700.00	2192.40	2295	0
15	Sundries	Ls	1	0	0.00	0.00	0	0
						7499.40	6200.75	0

						100%	10%	
SINGLE POLE CUT POINT STRUCTURE FOR 11KV LINE ON RSJ 11 M POLE (Act-No 924)								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	10%	Total Amt (10%)
1	RSJ 152x152, 11 m long	No.	1	0	3150.00	3150.00	315	0
2	M.S.Cut Point Channel with complete set	set	1	0	650.00	650.00	65	0
3	Strain Hardware for Dog0.1 or Equ.AAAC.	No.	6	0	20.00	120.00	2	0
4	Disc Insulator 11 KV 70 KN	No.	6	0	30.00	180.00	3	0
5	H.T.Stay Set	No.	2	0	400.00	800.00	40	0
6	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	13	0	5.00	65.00	0.5	0
7	Earthing Sets H.T	No.	1	0	285.00	285.00	28.5	0
8	G.I.Wire 8 SWG/ 6 SWG	Kg.	2	0	4.00	8.00	0.4	0
9	G.I.Barbed Wire A' type.	Kg.	2	0	3.00	6.00	0.3	0
10	Black Bituminus Paint	Ltr.	0.5	0	10.00	5.00	1	0
11	Red Oxide Paint for 1 coats	Ltr.	1	0	14.00	14.00	1.4	0
12	Aluminium Paint for 1 coat	Ltr.	1	0	14.00	14.00	1.4	0
13	Danger Board in yard.	No.	1	0	10.00	10.00	1	0
14	Concreting ration 1:3 6	Cmt.	0.812	0	2700.00	2192.40	270	0
15	Sundries	Ls	1	0	0.00	0.00	0	0
						7499.40	729.5	0

						100%	5%	
SINGLE POLE CUT POINT STRUCTURE FOR 11KV LINE ON RSJ 11 M POLE (Act-No 924)								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	5%	Total Amt (5%)
1	RSJ 152x152, 11 m long	No.	1	0	3150.00	3150.00	157.5	0
2	M.S.Cut Point Channel with complete set	set	1	0	650.00	650.00	32.5	0
3	Strain Hardware for Dog0.1 or Equ.AAAC.	No.	6	0	20.00	120.00	1	0
4	Disc Insulator 11 KV 70 KN	No.	6	0	30.00	180.00	1.5	0
5	H.T.Stay Set	No.	2	0	400.00	800.00	20	0
6	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	13	0	5.00	65.00	0.25	0
7	Earthing Sets H.T	No.	1	0	285.00	285.00	14.25	0
8	G.I.Wire 8 SWG/ 6 SWG	Kg.	2	0	4.00	8.00	0.2	0
9	G.I.Barbed Wire A' type.	Kg.	2	0	3.00	6.00	0.15	0
10	Black Bituminus Paint	Ltr.	0.5	0	10.00	5.00	0.5	0
11	Red Oxide Paint for 1 coats	Ltr.	1	0	14.00	14.00	0.7	0
12	Aluminium Paint for 1 coat	Ltr.	1	0	14.00	14.00	0.7	0
13	Danger Board in yard.	No.	1	0	10.00	10.00	0.5	0
14	Concreting ration 1:3 6	Cmt.	0.812	0	2700.00	2192.40	135	0
15	Sundries	Ls	1	0	0.00	0.00	0	0
						7499.40	364.75	0

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory

-

						100%	85%	
DOUBLE POLE STRUCTURE(cut point) OF- 11 KV LINE USING11 M LONG RSJ POLE (Act-No 922)								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	85%	Total Amt (85%)
1	RSJ 116x100, 11 m long	No.	2	0	2500.00	5000.00	2125	0
2	M.S. Flats for stay & C clamps(50 X 10mm)	Nos	14	0	10.00	140.00	8.5	0
3	MS Top Channel 100x50x6 mm	No	2	0	250.00	500.00	212.5	0
4	M.S. Bottom Channel 75x40x6 mm	No	2	0	250.00	500.00	212.5	0
5	MS Bracing angle 50x50x6 mm	No	2	0	150.00	300.00	127.5	0
6	Strain Hardware for Dog0.1 or Equ.AAAC.	No.	6	0	20.00	120.00	17	0
7	Disc Insulator 11 KV 70 KN	No.	6	0	30.00	180.00	25.5	0
8	H.T.Stay Set	No.	2	0	400.00	800.00	340	0
9	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	25	0	5.00	125.00	4.25	0
10	Earthing Sets H.T	No	2	0	285.00	570.00	242.25	0
11	G.I.Wire 8 SWG/ 6 SWG	kg.	6	0	4.00	24.00	3.4	0
12	G.I.Barbed Wire A' type.	kg.	7	0	3.00	21.00	2.55	0
13	Danger Board in yard.	No.	2	0	10.00	20.00	8.5	0
14	Black Bituminus Paint	Ltr.	2	0	10.00	20.00	8.5	0
15	Red Oxide Paint for 1 coats	Ltr.	6	0	14.00	84.00	11.9	0
16	Aluminium Paint for 1 coat	Ltr.	4	0	14.00	56.00	11.9	0
17	Concreting ration 1:3 6	Cmt.	0.903	0	2700.00	2438.73	2295	0
18	Sundries	L.S.	1	0	0.00	0.00	0	0
						10898.73	5656.75	0

						100%	10%	
DOUBLE POLE STRUCTURE(cut point) OF- 11 KV LINE USING11 M LONG RSJ POLE (Act-No 922)								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	10%	Total Amt (10%)
1	RSJ 116x100, 11 m long	No.	2	0	2500.00	5000.00	250	0
2	M.S. Flats for stay & C clamps(50 X 10mm)	Nos	14	0	10.00	140.00	1	0
3	MS Top Channel 100x50x6 mm	No	2	0	250.00	500.00	25	0
4	M.S. Bottom Channel 75x40x6 mm	No	2	0	250.00	500.00	25	0
5	MS Bracing angle 50x50x6 mm	No	2	0	150.00	300.00	15	0
6	Strain Hardware for Dog0.1 or Equ.AAAC.	No.	6	0	20.00	120.00	2	0
7	Disc Insulator 11 KV 70 KN	No.	6	0	30.00	180.00	3	0
8	H.T.Stay Set	No.	2	0	400.00	800.00	40	0
9	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	25	0	5.00	125.00	0.5	0
10	Earthing Sets H.T	No	2	0	285.00	570.00	28.5	0
11	G.I.Wire 8 SWG/ 6 SWG	kg.	6	0	4.00	24.00	0.4	0
12	G.I.Barbed Wire A' type.	kg.	7	0	3.00	21.00	0.3	0
13	Danger Board in yard.	No.	2	0	10.00	20.00	1	0
14	Black Bituminus Paint	Ltr.	2	0	10.00	20.00	1	0
15	Red Oxide Paint for 1 coats	Ltr.	6	0	14.00	84.00	1.4	0
16	Aluminium Paint for 1 coat	Ltr.	4	0	14.00	56.00	1.4	0
17	Concreting ration 1:3 6	Cmt.	0.903	0	2700.00	2438.73	270	0
18	Sundries	L.S.	1	0	0.00	0.00	0	0
						10898.73	665.5	0

						100%	5%	
DOUBLE POLE STRUCTURE(cut point) OF- 11 KV LINE USING11 M LONG RSJ POLE (Act-No 922)								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	5%	Total Amt (5%)
1	RSJ 116x100, 11 m long	No.	2	0	2500.00	5000.00	125	0
2	M.S. Flats for stay & C clamps(50 X 10mm)	Nos	14	0	10.00	140.00	0.5	0
3	MS Top Channel 100x50x6 mm	No	2	0	250.00	500.00	12.5	0
4	M.S. Bottom Channel 75x40x6 mm	No	2	0	250.00	500.00	12.5	0
5	MS Bracing angle 50x50x6 mm	No	2	0	150.00	300.00	7.5	0
6	Strain Hardware for Dog0.1 or Equ.AAAC.	No.	6	0	20.00	120.00	1	0
7	Disc Insulator 11 KV 70 KN	No.	6	0	30.00	180.00	1.5	0
8	H.T.Stay Set	No.	2	0	400.00	800.00	20	0
9	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	25	0	5.00	125.00	0.25	0
10	Earthing Sets H.T	No	2	0	285.00	570.00	14.25	0
11	G.I.Wire 8 SWG/ 6 SWG	kg.	6	0	4.00	24.00	0.2	0
12	G.I.Barbed Wire A' type.	kg.	7	0	3.00	21.00	0.15	0
13	Danger Board in yard.	No.	2	0	10.00	20.00	0.5	0
14	Black Bituminus Paint	Ltr.	2	0	10.00	20.00	0.5	0
15	Red Oxide Paint for 1 coats	Ltr.	6	0	14.00	84.00	0.7	0
16	Aluminium Paint for 1 coat	Ltr.	4	0	14.00	56.00	0.7	0
17	Concreting ration 1:3 6	Cmt.	0.903	0	2700.00	2438.73	135	0
18	Sundries	L.S.	1	0	0.00	0.00	0	0
						10898.73	332.75	0

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory

						100%	85%	
River crossing with 55 sqmm overhead conductor on 152X152M M,13 mtr RSJ pole as per sketch for one span of 100 mtr. (Act No 919)								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	85%	Total Amt (85%)
1	RSJ 152x152, 13 m long	No.	4	4	4000.00	16000.00	3400	13600
2	M.S.Bottom Channel 75x40x6 mm	no	2	2	250.00	500.00	212.5	425
3	MS Top Channel 100x50x6 mm	no	2	2	250.00	500.00	212.5	425
4	MS cross bracing angle 50x50x6 mm	no	2	2	150.00	300.00	127.5	255
5	M.S. Flats for stay & C clamps(50 X 10mm)	no	14	14	10.00	140.00	8.5	119
6	AAAC 55 mm2	Mtr	330	330	4.00	1320.00	3.4	1122
7	11 kV Pin Insulators with G.I. Pins	NO.	6	6	15.00	90.00	12.75	76.5
8	Disc Insulator 11 KV 45 KN	NO.	12	12	30.00	360.00	25.5	306
9	Strain Hardware for Dog0.1 or Equ.AAAC.	No.	12	12	20.00	240.00	17	204
10	H.T.Stay Set	Set	4	4	400.00	1600.00	340	1360
11	G.I.Stay Wire 7/4mm(8 SWG)	kg.	25	25	5.00	125.00	4.25	106.25
12	Earthing Sets H.T	No.	4	4	285.00	1140.00	242.25	969
13	Danger Board in yard.	No.	4	4	10.00	40.00	8.5	34
14	G.I.Wire 8 SWG/ 6 SWG	Kg.	25	25	4.00	100.00	3.4	85
15	G.I.Barbed Wire A' type.	kg.	30	30	3.00	90.00	2.55	76.5
16	Black Bituminus Paint	Ltr.	2	2	10.00	20.00	8.5	17
17	Red Oxide Paint for 1 coats	Ltr.	6	6	14.00	84.00	11.9	71.4
18	Aluminium Paint for 1 coat	Ltr.	4	4	14.00	56.00	11.9	47.6
19	Concreting ration 1:3 6	CMT.	2.653	3	2700.00	7163.10	2295	6088.635
a)	RABIT To RABIT or equivalent AAAC	No	12	12	11.00	132.00	9.35	112.2
						30000.10	6957.25	25500.085

						100%	10%	
River crossing with 55 sqmm overhead conductor on 152X152M M,13 mtr RSJ pole as per sketch for one span of 100 mtr. (Act No 919)								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	10%	Total Amt (10%)
1	RSJ 152x152, 13 m long	No.	4	4	4000.00	16000.00	400	1600
2	M.S.Bottom Channel 75x40x6 mm	no	2	2	250.00	500.00	25	50
3	MS Top Channel 100x50x6 mm	no	2	2	250.00	500.00	25	50
4	MS cross bracing angle 50x50x6 mm	no	2	2	150.00	300.00	15	30
5	M.S. Flats for stay & C clamps(50 X 10mm)	no	14	14	10.00	140.00	1	14
6	AAAC 55 mm2	Mtr	330	330	4.00	1320.00	0.4	132
7	11 kV Pin Insulators with G.I. Pins	NO.	6	6	15.00	90.00	1.5	9
8	Disc Insulator 11 KV 45 KN	NO.	12	12	30.00	360.00	3	36
9	Strain Hardware for Dog0.1 or Equ.AAAC.	No.	12	12	20.00	240.00	2	24
10	H.T.Stay Set	Set	4	4	400.00	1600.00	40	160
11	G.I.Stay Wire 7/4mm(8 SWG)	kg.	25	25	5.00	125.00	0.5	12.5
12	Earthing Sets H.T	No.	4	4	285.00	1140.00	28.5	114
13	Danger Board in yard.	No.	4	4	10.00	40.00	1	4
14	G.I.Wire 8 SWG/ 6 SWG	Kg.	25	25	4.00	100.00	0.4	10
15	G.I.Barbed Wire A' type.	kg.	30	30	3.00	90.00	0.3	9
16	Black Bituminus Paint	Ltr.	2	2	10.00	20.00	1	2
17	Red Oxide Paint for 1 coats	Ltr.	6	6	14.00	84.00	1.4	8.4
18	Aluminium Paint for 1 coat	Ltr.	4	4	14.00	56.00	1.4	5.6
19	Concreting ration 1:3 6	CMT.	2.653	3	2700.00	7163.10	270	716.31
a)	RABIT To RABIT or equivalent AAAC	No	12	12	11.00	132.00	1.1	13.2
						30000.10	818.5	3000.01

						100%	5%	
River crossing with 55 sqmm overhead conductor on 152X152M M,13 mtr RSJ pole as per sketch for one span of 100 mtr. (Act No 919)								
Sr.No.	Description of Material	Unit	Qty.	Total Qty	Rate	Amount	5%	Total Amt (5%)
1	RSJ 152x152, 13 m long	No.	4	4	4000.00	16000.00	200	800
2	M.S.Bottom Channel 75x40x6 mm	no	2	2	250.00	500.00	12.5	25
3	MS Top Channel 100x50x6 mm	no	2	2	250.00	500.00	12.5	25
4	MS cross bracing angle 50x50x6 mm	no	2	2	150.00	300.00	7.5	15
5	M.S. Flats for stay & C clamps(50 X 10mm)	no	14	14	10.00	140.00	0.5	7
6	AAAC 55 mm2	Mtr	330	330	4.00	1320.00	0.2	66
7	11 kV Pin Insulators with G.I. Pins	NO.	6	6	15.00	90.00	0.75	4.5
8	Disc Insulator 11 KV 45 KN	NO.	12	12	30.00	360.00	1.5	18
9	Strain Hardware for Dog0.1 or Equ.AAAC.	No.	12	12	20.00	240.00	1	12
10	H.T.Stay Set	Set	4	4	400.00	1600.00	20	80
11	G.I.Stay Wire 7/4mm(8 SWG)	kg.	25	25	5.00	125.00	0.25	6.25
12	Earthing Sets H.T	No.	4	4	285.00	1140.00	14.25	57
13	Danger Board in yard.	No.	4	4	10.00	40.00	0.5	2
14	G.I.Wire 8 SWG/ 6 SWG	Kg.	25	25	4.00	100.00	0.2	5
15	G.I.Barbed Wire A' type.	kg.	30	30	3.00	90.00	0.15	4.5
16	Black Bituminus Paint	Ltr.	2	2	10.00	20.00	0.5	1
17	Red Oxide Paint for 1 coats	Ltr.	6	6	14.00	84.00	0.7	4.2
18	Aluminium Paint for 1 coat	Ltr.	4	4	14.00	56.00	0.7	2.8
19	Concreting ration 1:3 6	CMT.	2.653	3	2700.00	7163.10	135	358.155
a)	RABIT To RABIT or equivalent AAAC	No	12	12	11.00	132.00	0.55	6.6
						30000.10	409.25	1500.005

For Ashoka Endurance Road Developer Pvt Ltd

For LK Electricals

Authorized Signatory

Authorized Signatory